BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2021-22/OW/WORK_INDENT50352

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/15/2021-22, Date: 18-02-2022

Name of Work:Improvements to footpath and drains in Ward No 08, Kodigehalli

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of SHARATH J N (SRI CHOWDESHWARI CONSTRUCTIONS)	
				In Figures	In Words
1	63.75	Removing & Refixing stone slabs of drains and pointing in C.M (1:3)	sqm	80.0	Rupees Eighty Only
2	257.58	Earthwork excavation by manual means for roads, drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications	cum	150.0	Rupees One Hundred Fifty Only
3	31.54	Providing and laying Plain cement concrete 1:3:6 mix with OPC 220kgs with crushed stone aggregate 40 mm and down size graded granite metal coarse aggregates @0.892Cum and fine aggregates @ 0.465Cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM curing complete as per specifications. Specification	cum	4500.0	Rupees Four Thousand Five Hundred Only
4	4.24	Providing T.M.T bars Fe 500 steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications	MT	80000.0	Rupees Eighty Thousand Only
5	73.6	Providing laying plain/ reinforced cement concrete for side Drains Using M20 nominal mix Concrete with OPC at 300kgs.With 20mm and Down size granite metal coarse aggregate at 0.69Cum and fine aggregate at 0.43Cum Machne mixed, well compacted for wall and Bottom including centering shuttering,cost of materials,HOM of Machinery,Curing Etc.,Complete Excluding cost of Steel as per morth MORTH specification No. 1500, 1700, 2200. Including Cost of material, Labour, HOM complete as per Specification WALL & Bottom thickness 15Cm	cum	6500.0	Rupees Six Thousand Five Hundred Only
6	188.69	Providing and Fixing Pre cast covering Slab 100mm thick made out of CC, jelly 20mm Down size with steel reinforcement including form work,curing,including cost of alll materials, labour,hire charges of machinery, loading, unloading, lead and lift,transportation etc ,complete.As per Engineer incharge. (Data Rate)	sqm	1810.05	Rupees One Thousand Eight Hundred Ten and Five Paise Only
7	28.8	Supply and fixing Precast reinforced concrete slab 200mm thick including cost of reinforcement as per design and drawing, material cost, transportation, hire charges of machinery, machine cutting the vertical face to get plain even surface etc., complete with all leads and lift conveynce charges, labour charges inclusive of cost of all materials.	sqm	5000.0	Rupees Five Thousand Only

Sharath

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92